



DRAWN:	DATE:	APPROVED:
		CP
REVISED:	DATE:	APPROVED:
GL	8-28-02	

TITLE:  
 AUTO-THROWOVER/w  
 900 AMP  
 LINE TAP SWITCHES

**GARLAND**  
 POWER & LIGHT  
 STANDARD NO.  
 OH-980B

**CONSTRUCTION STANDARD NO. : OH-980****TITLE: AUTO THROWOVER W/900 AMP  
LINE TAP SWITCHES  
Disconnects to be determined by Engineer**

REV. DATE: 6/19/2003

**Total Material Cost : \$8,903.54**

PIC. #	DESCRIPTION	IBM NO.	QTY.	TOTAL COST
1	SWITCH, LINE TAP, BRIDGES TYPE LER, 900 AMP	286-80-53530	6	\$0.00
2	LUG TERMINAL #500 MCM STR CU TYPE YA	285-49-17610	6	\$16.99
3	ELECTRIC CONDUIT 2" 10' PVC TYPE 1 SCH 40 NSE PIPE TYPE	285-14-72122	3	\$9.03
4	#2 CU BARE HD 7 STR	280-09-21051	15	\$7.79
5	BIRD GUARD COVER, FARGO GS-555	285-39-24101	6	\$17.16
6	STRAP 2" 2 HOLE RIGID	285-14-11275	6	\$1.28
8	CABLE, CU, 500MCM, 37 STR, SNGL COND., 600 V, TYPE RHH, RHW, USE	280-42-14100	30	\$114.34
9	BOLT HEX HD 1/2" X 2" STN/STL	320-09-11261	12	\$10.20
10	WASHER BELLEVILLE 9/16" STN/ST	320-09-30130	24	\$13.14
11	NUT HEX 1/2" STN/STL	320-09-13051	12	\$3.60
15	AUTO THROWOVER - PROVIDED BY SUBSTATION	000-00-00031	1	\$4,327.00
16	BRACKET, POLE MOUNT - PROVIDED BY SUBSTATION	000-00-00032	1	\$1,000.00
17	"S" CONTROLLER - PROVIDED BY SUBSTATION	000-00-00033	1	\$3,343.00
18	#12 WIRE; 6 CONDUCTOR	000-00-00034	40	\$40.00