



POLE MOUNT BRACKET

ENGINEER TO DECIDE
CONNECTOR ON FEEDER

REMOVAL ONLY

DRAWN:	DATE:	APPROVED:
REVISD:	DATE:	APPROVED:
GL	8-28-02	CP

TITLE:
 AUTO-THROWOVER/w
 600 AMP WOOD ARM
 MOUNT SWITCHES

GARLAND
 POWER & LIGHT
 STANDARD NO.
 OH-981

CONSTRUCTION STANDARD NO. : OH-981

TITLE: THROWOVER 600 AMP - REMOVAL/REPAIR ONLY

REV. DATE: 6/5/2003

Total Material Cost : \$9,729.30

PIC. #	DESCRIPTION	IBM NO.	QTY.	TOTAL COST
1	DISCONNECT 600 AMP SINGLE PHASE W/POST INSULATOR AB CHANCE	286-80-54110	6	\$723.00
2	LUG TERMINAL #500 MCM STR CU TYPE YA	285-49-17610	12	\$40.20
3	ELECTRIC CONDUIT 2" 10' PVC TYPE 1 SCH 40 NSE PIPE TYPE	285-14-72122	3	\$12.48
4	#2 CU BARE HD 7 STR	280-09-21051	15	\$7.20
5	BIRD GUARD COVER, FARGO GS-555	285-39-24101	6	\$16.62
6	STRAP 2" 2 HOLE RIGID	285-14-11275	6	\$1.26
7	ROD GROUNDING 5/8" X 8'	285-36-15108	1	\$6.23
8	CABLE, CU, 500MCM, 37 STR, SNGL COND., 600 V, TYPE RHH, RHW, USE	280-42-14100	30	\$71.40
9	BOLT HEX HD 1/2" X 2" STN/STL	320-09-11261	24	\$20.40
10	WASHER BELLEVILLE 9/16" STN/ST	320-09-30130	48	\$45.60
11	NUT HEX 1/2" STN/STL	320-09-13051	24	\$7.20
12	SERVICE HEAD 2" CLAMP ON	285-14-65226	1	\$5.00
13	CLAMP GROUND ROD 5/8"	285-13-16025	1	\$0.58
14	CONNECTOR CRIMPIT CU. #6 - #6	285-18-17010	1	\$0.27
15	AUTO THROWOVER - PROVIDED BY SUBSTATION	000-00-00031	1	\$4,327.00

16	BRACKET, POLE MOUNT - PROVIDED BY SUBSTATION	000-00-00032	1	\$1,000.00
17	"S" CONTROLLER - PROVIDED BY SUBSTATION	000-00-00033	1	\$3,343.00
18	#12 WIRE; 6 CONDUCTOR	000-00-00034	40	\$40.00
19	#477 ACSR HAWK 26/7 STR	280-07-13125	30	\$18.60
20	LUG TERMINAL 2H PAD COMPR 477 MCM ACSR, BLACKBURN AL S-28	285-49-17524	6	\$43.26