

CONSTRUCTION STANDARD NO. : UG-2430DA**TITLE: THREE PHASE PADMOUNT XFMR DEAD FRONT - LOOP
FEED**

REV. DATE: 3/28/2006

PIC. #	DESCRIPTION	IBM NO.	QTY.
1	ELBOW LOADBREAK #2/O 15KV 200A AL/CU CABLE .220 MIL INSULATION	285-19-19163	6
2	ARRESTER, BUSHING, M.O.V., 9/10 KV, FOR 200 AMP LOAD BREAK ELBOW & BUSHING	286-04-20000	6
3	FAULT INDICATOR LOAD TRACKER PADMOUNT - SINGLE PHASE	286-30-10345	6
4	LUG TRANSFORMER GROUNDING 8 SOL TO 2/O STR	285-49-17325	2
5	#2 CU BARE HD 7 STR	280-09-21051	15
6	CLAMP GROUND ROD 5/8"	285-13-16025	1
7	#2 HOMAC LUG - AL	285-54-17537	1