



ENGINEERING NOTE:
 NEW CONSTRUCTION
 ADD PEDESTAL & #6
 SPLIT BOLT

INSTALL FUSE KIT
 IN PEDESTAL

6

POLECRETE FOAM

GRADE

6'

7

12" DIA. HOLE MAX.

TITLE:

1 90 SERVICE ROAD
 LIGHTING

GARLAND
 POWER & LIGHT

DRAWN BY: GL	DATE: 1/31/05	APPROVED BY: CP
REVISED BY: JC	DATE: 3/23/05	APPROVED BY:

STANDARD NO.:
UG-2923

CONSTRUCTION STANDARD NO. : UG-2923**TITLE: STREET LIGHTING - GEORGE BUSH TOLLWAY**

REV. DATE: 8/1/2005

Total Material Cost : \$1,217.69

PIC. #	DESCRIPTION	IBM NO.	QTY.	TOTAL COST
1	POLE FIBERGLASS 46', ST LT, GEORGE BUSH HWY	528-67-82000	1	\$500.00
2	LUMINAIRE, GEORGE BUSH HWY ONLY	528-50-80200	1	\$536.00
3	LAMP HIGH PRESSURE SODIUM 400W	528-40-12140	1	\$28.64
4	FUSE, NON-RENEWABLE, 8 AMP. 600 VOLT	285-32-21500	1	\$2.86
5	CONNECTOR FUSED KIT	285-32-60100	1	\$5.21
6	POLECRETE FOAM POLE STABILIZER 3 GAL	210-13-07100	2	\$137.58
7	ROD GROUNDING 5/8" X 8'	285-36-15108	1	\$7.40